BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

DRAFT TENDER SCHEDULE –'B'

Item No:
Original / Duplicate

Name of Work:- Construction of RCC drain at Kenchenahalli and Nagenahalli layout ISRO layout Harohalli and surrounding areas in chowdeshwari ward no -02 of yelahanka Sub division

Sl. No	Description	Unit	Approved Qty	Approved Rate	Rates in words
1	Removing and resetting of footpath slab	sqm	381.60	208.82	Rupees Two Hundred Eight and Paise Eighty Two Only
2	KSRRB300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per	Cum	1688.33	211.79	Rupees Two Hundred Eleven and Paise Seventy Nine Only
3	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications.	Cum	287.93	5505.64	Rupees Five Thousand Five Hundred Five and Paise Sixty Four Only

Sl. No	Description	Unit	Approved Qty	Approved Rate	Rates in words
4	KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications and directions of the Engineer in charge.	tonne	39.39	72326.98	Rupees Seventy Two Thousand Three Hundred Twenty Six and Paise Ninety Eight Only
5	Providing and laying plain/reinforced cement concrete for side drains Wall & bottom thickness 15cm using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500,1700, 2200. including cost of materials, labour, HOM complete as per specifications.	Cum	649.63	7070.20	Rupees Seven Thousand Seventy and Paise Twenty Only
6	Supplying and fixing precast reinforced concrete slab 10 cm thick of mix M20 using 20mm and downsize graded granite metal using reinforcement 10mm dia steel at 150mm C/c both ways cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of cost of all materials(data Rate enclosed)	Sqm	1215.00	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
7	Providing and laying Pre Cast Drain Cover slabs of 250mm thick of mix M20 using graded granite jelly 20mm down size with steel reinforcement, including from work, lift charges, curing and concrete finished surfaces on both side etc. complete and as per drawing and direction of Engineer-in-charge of work (data Rate enclosed)	Sqm	32.85	5418.00	Rupees Five Thousand Four Hundred Eighteen Only
8	Providing and fixing Pre cast solid concrete kerb stones of size 450 x 200 x 400 mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete.	Nos	2112.00	477.00	Rupees Four Hundred Seventy Seven Only

Bruhat Bengaluru

Sl. No	Description	Unit	Approved Qty	Approved Rate	Rates in words
9	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	475.00	84.80	Rupees Eighty Four and Paise Eighty Only
10	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications.Clause 502 of MORTH V revision	Sqm	6415.00	33.92	Rupees Thirty Three and Paise Ninety Two Only
11	KSRRB 500-2. Cleaning the existing black topped surface with Sqm brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM complete as per specifications. Clause 501 of MORTH V revision	Sqm	6415.00	5.30	Rupees Five and Paise Thirty Only
12	KSRRB M500-17. Providing and laying Dense Graded Bituminous Macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications. MORTH Specification No. 507. Using 100/120 TPH capacity HMP with sensor paver Gr-II (50 mm to 75mm) with 4.5% VG-30 Bitumen.	Cum	48.11	7620.34	Rupees Seven Thousand Six Hundred Twenty and Paise Thirty Four Only
13	KSRRB M500-10. Providing and applying tack coat using 80/100 grade Sqm bitumen(VGlO) in boiler fitted with spray set distributor at the rate of 0.25 kg per sqm on the existing prepared bituminous surface (primed surface) cleaned with mechanical broom, complete as per specifications. Clause 503 of MORTH V revision	Sqm	6415.00	12.72	Rupees Twelve and Paise Seventy Two Only

Bruhat Bengaluru Mahanagara

Sl. No	Description	Unit	Approved Qty	Approved Rate	Rates in words
14	Providing and laying bituminous concrete 40mm thick with hot mix plant, using 40-60 TPH capacity HMP with mechanical paver grading II (30-45mm) with 5.4 % of modified bituminous binder consisting of 4.97% of VG-30 bitumen (60/70 grade) and 0.43% of plastomeric thermoplastics (waste plastic) crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision as per IRC SP-53-2015.	Cum	256.60	8699.42	Rupees Eight Thousand Six Hundred Ninety Nine and Paise Forty Two Only
15	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803	Sqm	408.50	454.74	Rupees Four Hundred Fifty Four and Paise Seventy Four Only

Sl. No	Description	Unit	Approved Qty	Approved Rate	Rates in words
16	KSRRB M800-35. Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS(Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/ NH/33023/10-97 - DO III Dt 11.06.1997. The height, width and length shall not exceed 50 mm, 100 mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 mm and height not less than 30 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by the engineer.	Nos	604.00	357.22	Rupees Three Hundred Fifty Seven and Paise Twenty Two Only
17	KSRRB M800-35. Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS(Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/ NH/33023/10-97 - DO III Dt 11.06.1997. The height, width and length shall not exceed 50 mm, 100 mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the	Nos	2.88	1963.12	Rupees One Thousand Nine Hundred Sixty Three and Paise Twelve Only

Sl. No	Description	Unit	Approved Qty	Approved Rate	Rates in words
18	Direction and Place Identification Signs with size morethan 0.9 Size Board: Providing and erecting direction and place identification retro -reflectorised sign as per IRC:67 made of high i ntensity grade sheeting vide Clause 801.3, fixed over aluminium sheeting, 2 mm thick with area not exceeding 0.9 sqm supported on a mild steel single angle iron post 75 x 75 x 6 mm , 2 Nos. firmly fixed to the ground by means of properly designed foundation with M 15 grade cement concrete 45 x 45 x 60 cm, 60 cm below ground level as per approved drawing.	sqm	3.24	7557.80	Rupees Seven Thousand Five Hundred Fifty Seven and Paise Eighty Only

"No correction NIL"
"DTS Approved"

Executive Engineer,
Yelahanka Division,
BBMP, Bangalore.

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ.